


To be read with Licence No. 108 of 2023 dated 15/09/2023

AREA STATEMENT							
S.No.		PERMISSIBLE			PROPOSED		
		%	ACRES	SQM	ACRES	%	SQM
1	NET PLANNED AREA		12.500	50585.705			
2	MAX PERMISSIBLE AREA UNDER PLOTTING	61.00%	7.625	30857.280	6.819	54.55%	27595.331
3	COMMERCIAL AREA	4.00%	0.500	2023.428	0.500	4.00%	2023.187
4	AREA FOR COMMON FACILITIES TO BE HANDED OVER TO GOVT.	10.00%	1.250	5058.571	1.250	10.00%	5060.212
5	MIN GREEN AREA	7.50%	0.938	3793.928	0.949	7.59%	3840.358
6	NO. OF PLOTS						224
7	OCCUPANCY PER DWELLING PLOT						13.50 P/PLOT
8	TOTAL POPULATION						3024 PERSONS
9	DENSITY	240-400 PPA					242 PPA

GREEN AREA CALCULATION			
S.No.	Green Number	Sqm	Acres
1	Green-1	278.015	0.069
2	Green-2	139.750	0.035
3	Green-3	160.440	0.040
4	Green-4	2510.677	0.620
5	Green-5	359.776	0.089
6	Green-6	391.701	0.097
	<b>Total</b>	<b>3840.358</b>	<b>0.949</b>

PLOT DETAILS						
Plot Type	Plot No.	Width (m)	Length (m)	Area (Sq.m.)	No.	Total Area (Sq.m.)
A	P1 - P155	8.65	15.00	129.75	155	20111.25
	P156 - P187	7.00	15.00	105.00	32	3360.00
B	P203 - P223	7.00	15.00	105.00	21	2205.00
	P198 - P201	7.00	15.00	105.00	4	420.00
C	P202	8.35	15.00	125.25	1	125.25
D	P224	9.05	15.00	135.75	1	135.75
E	P188 - P191	7.00	17.03	119.21	4	476.84
	P194 - P197	7.00	17.03	119.21	4	476.84
F	P192 - P193	8.35	17.03	142.20	2	284.40
	<b>Total</b>				<b>224</b>	<b>27595.331</b>
						<b>Acres 6.819</b>



- That this Layout Plan shall be read in conjunction with the clauses appearing on the agreement executed under Rule 11 and the bilateral agreement.
- That the plotted area of the colony shall not exceed 65% of the net planned area of the colony. The entire area reserved for commercial purposes shall be taken as plotted for calculation of the area under plots.
- That the demarcation plans as per site of all the Residential Plots and Commercial sites shall be got approved from this Department and construction on these sites shall be governed by the Haryana Building Code, 2017 and the Zoning Plan approved by the Director General, Town & Country Planning, Haryana.
- That for proper planning and integration of services in the area adjacent to the colony, the colonizer shall abide by the directions of the DG, TCP for the modification of layout plans of the colony.
- That the revenue rasta falling in the colony shall be kept free for circulation/movement as shown in the layout plan.
- That the colonizer shall abide by the directions of the DG, TCP, Haryana and accordingly shall make necessary changes in the layout plan for making any adjustment in the alignment of the peripheral roads, internal road circulation or for proper integration of the planning proposals of the adjoining areas.
- That no property/plot shall derive access directly from the carriage way of 30 metres or wider sector road if applicable.
- All green belts provided in the layout plan within the licenced areas of the colony shall be developed by the colonizer. All other green belts outside the licenced area shall be developed by the Haryana Urban Development Authority/colonizer on the directions of the Director General, Town and Country planning, Haryana or in accordance with terms and conditions of the agreements of the licence.
- At the time of demarcation plan, if required percentage of organized open space is reduced, the same will be provided by the colonizer in the licenced area.
- No plot will derive an access from less than 9 metres wide road would mean a minimum clear width of 9 metres between the plots.
- Any excess area over and above the permissible 4% under commercial use shall be deemed to be open space.
- The portion of the sector/development plan roads / green belts as provided in the Development Plan if applicable, which form part of the licenced area shall be transferred free of cost to the government on the lines of Section 3(3)(a)(iii) of the Act No.8 of 1975.
- That the odd size plots are being approved subject to the conditions that these plots should not have a frontage of less than 75% of the standard frontage when demarcated.
- That you will have no objection to the regularization of the boundaries of the licence through give and take with the land that IESVP is finally able to acquire in the interest of planned development and integration of services. The decision of the competent authority shall be binding in this regard.
- That the rain water harvesting system shall be provided as per Central Ground Water Authority norms/Haryana Govt. notification as applicable.
- That the colonizer/owner shall use only Light-Emitting Diode lamps (LED) fitting for internal lighting, as well as Campus lighting.
- That the colonizer/owner shall ensure the installation of Solar Power Plant as per provisions of Haryana Solar Power Policy, 2016 issued by Haryana Government Renewable Energy Department vide Notification No. 19/4/2016-5 Power dated 14.03.2016
- That the colonizer/owner shall ensure the installation of Solar Photovoltaic Power Plant as per the provisions of order No.22/52/2005-5 Power dated 21.03.2016 issued by Haryana Government Renewable Energy Department.
- That the colonizer/owner shall strictly comply with the directions issued vide Notification No. 19/6/2016-5P dated 31.03.2016 issued by Haryana Government Renewable Energy Department for enforcement of the Energy Conservation Building Codes.

(SANJAY NARANG) (R.S. BATHI) (HITESH SHARMA) (P.P. SINGH) (T.L. SATYAPRAKASH, IAS)  
 ATP (HQ) DTP (HQ) STP (M) HQ CTP (HR) DG, TCP (HR)

(RAM AVTAR BASSI)  
 JD (HQ)

	COMMERCIAL BLOCK
	LAND TO BE HANDED OVER TO GOVERNMENT FOR AMENITIES
	GREEN AREA
	STP (450 SQMT.) UGT (200 SQMT.)
	M.B. MILK & VEGETABLE BOOTH (5.50X5.00 M.)

CLIENT / OWNER	
<b>M/S LION INFRADEVELOPERS LLP.</b>	
PROJECT	
Layout plan of Affordable Residential Plotted Colony (Under DDJAY scheme 2016) over an area measuring 12.50 acres. <small>(LOI memo no.LC-5105/UE (DS)/2023/21610 dated 04.07.2023)</small> <small>[Rect/Kills no. 132/25/22 143/5/22.6 142/9/2.11 143/14/2.15/1 133/20/1/1,2/2/2 142/11/10,12,13, 143/4/2/2, 7/1/1, 142/9/1, 133/19/1/1, 22, 142/2 TOTAL AREA 100 KANAL 0 MARLA OR TOTAL LAND 12.50 ACRES FALLING IN THE REVENUE ESTATE OF VILLAGE SOHNA, SECTOR-6, SOHNA, DISTRICT GURUGRAM, HARYANA.</small> <small>DEVELOPED BY:- M/S LION INFRA DEVELOPERS LLP.</small>	
OWNER/AUTH. SIGNATURE	ARCHITECT'S SIGNATURE
PRINCIPAL ARCHITECT	
<b>ACPL</b>	ISO 9001:2015 Architecture Management Planning
ACPL Design Ltd	E-24 South Extension -III, 4th Flr 112462705 New Delhi 110048, India +91 11 24642705 www.acplm.com   contact@acplm.com   +91 11 24620808
DRAWING TITLE	
<b>LAYOUT PLAN</b>	
DRAWING NO. A/01	SCALE: 1 : 100 DATE: AUG.-2023